



बैंक ऑफ महाराष्ट्र
Bank of Maharashtra

भारत सरकार का उद्यम
एक परिवार एक बैंक



बैंक ऑफ महाराष्ट्र
Bank of Maharashtra

भारत सरकार का उद्यम

एक परिवार एक बैंक

BANK OF MAHARASHTRA
LOKMNAGAL, 1501,
SHIVAJINAGAR, PUNE-411 005.

FINANCIAL BID

TENDER NO. AX1/CSD/11KV RMU SHIFTING/21-22

**TENDER DOCUMENT FOR "SUPPLY, INSTALLATION, ERECTION,
TESTING AND COMMISSIONING OF 11KV RMU & CABLES AT
BANK OF MAHARASHTRA PUNE"**



**PRICE BID
(BILL OF QUANTITIES)**

Description of Work: "SUPPLY, INSTALLATION, ERECTION, TESTING AND COMMISSIONING OF 11KV RMU & CABLES AT BANK OF MAHARASHTRA PUNE"

S No.	Description of Material	Unit	Qty	Rate Per Unit	Basic Amount	GST	Total Amount
1	Supplying 11 KV XLPE Cable 6.35/11KV grade 3C/185 sq mm as per MSEDCL Specification	Rmt	90				
2	Supplying 11 KV XLPE Cable 6.35/11KV grade 3C/300 sq mm as per MSEDCL Specification	Rmt	540				
3	Supplying 11 KV XLPE Cable 6.35/11KV grade 3C/240 sq mm as per MSEDCL Specification	Rmt	90				
4	Supplying 11 KV XLPE Cable 6.35/11KV grade 3C/95 sq mm as per MSEDCL Specification	Rmt	270				
5	Supplying 11KV,630 A,21kA/3sec,Oudoor Type, Extensible RMU with 3 Isolators & 1 Breaker as per MSEDCL Specification	No.	1				
6	Supplying 11KV,630 A,21kA/3sec,Oudoor Type, Extensible RMU with 2 Isolators & 2 Breaker as per MSEDCL Specification	No.	1				
7	Supplying 11KV,630 A,21kA/3sec,Oudoor Type, Extensible RMU with 3 Isolators & 2 Breaker as per MSEDCL Specification	No.	1				
8	Supplying 11 KV XLPE Cable 6.35/11KV grade 300 sq mm straight through joint Kit as per MSEDCL Specification	No.	6				
9	Supplying 11 KV XLPE Cable 6.35/11KV grade 240 sq mm straight through joint Kit as per MSEDCL Specification	No.	1				



10	Supplying 11 KV XLPE Cable 6.35/11KV grade 185 sq mm straight through joint Kit as per MSEDCL Specification	No.	1				
11	Supplying 11 KV XLPE Cable 6.35/11KV grade 95 sq mm straight through joint Kit as per MSEDCL Specification	No.	3				
12	Supplying 11 KV XLPE Cable 6.35/11KV grade indoor heat shrinkable 3C*185 sq mm straight through joint Kit as per MSEDCL Specification	No.	1				
13	Supplying 11 KV XLPE Cable 6.35/11KV grade indoor heat shrinkable 3C*240 sq mm straight through joint Kit	No.	1				
14	Supplying 11 KV XLPE Cable 6.35/11KV grade indoor heat shrinkable 3C*300 sq mm straight through joint Kit as per MSEDCL Specification	No.	6				
15	Supplying 11 KV XLPE Cable 6.35/11KV grade indoor heat shrinkable 3C*95 sq mm straight through joint Kit as per MSEDCL Specification	No.	3				
16	Supplying Earthing Sets HT	No.	15				
17	Construction of 3 nos. Earth Pits & secondary Earthing of all equipments as per IS 3043(1987)	Ls	1				
18.	Supply, installation of 450 mm ladder type cable tray with necessary bends along with all accessories & earthing of the same etc. complete	Rmt.	300				
19	Installation Cost of all materials as per MSEDCL specifications & supervision from S No. (1-18)	LS	1				



20	Removal of existing RMU from Site and shifting it to MSEDCL Store 5Km away.The scope includes dismantling, loading, unloading and handing over to the MSEDCL office of respective jurisdiction.	Ls	1				
21	Liason Charges MSEDCL	Ls	1				
TOTAL							

TOTAL AMOUNT Rs. _____ (excl GST)

TOTAL AMOUNT in words: Rs. _____ (excl GST)

(Signature of the authorized person with stamp of the firm/company)

Name of the authorized person:

Date:

Note

1. Supplying items from Sr. No. 1 to 18 includes scope of supplying, loading, unloading, transportation at site. Also, it shall include any charges of mathadi/local labour.
2. **Payment terms:** The payments shall be made as per the following terms and conditions:
 - i) 30% of the ordered value after the supply of the complete system at site and duly certified by the concerned officer of the Bank & MSEDCL as per the technical specification and terms and conditions specified in the contract.
 - ii) 50% of the ordered value after installation and commissioning of the system, along with the summary of Joint Commissioning & handing over certificate, indicating bill of material and successful commissioning duly countersigned by the designated Bank & MSEDCL officer
 - iii) 15% of the order value shall be released on completion of whole project to the satisfactory level of MSEDCL along with handing over to the MSEDCL.
 - iv) 5% of the order value for Defect Liability Period of 1 years from date of Commissioning. The security deposit may be converted to Bank guarantee.