

**PRICE BID**

<b>PRICE BID : SUPPLY, INSTALLATION, TESTING COMMISSIONING &amp; MAINTENANCE OF AIRCONDITIONES AT INDORE ZONE BANK OF MAHARASHTRA</b>					
<b>S No.</b>	<b>Work Description</b>	<b>Qty</b>	<b>UOM</b>	<b>Rate</b>	<b>Amount</b>
<b>HIGH SIDE WORKS(A)</b>					
1	Providing <b>2 TON Split 3 Star AC system of Inverter type</b> along with indoor & outdoor units. The condenser shall be of Copper.Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) with copper condenser.Specify: Make : Model No. :	18	Nos.		
2	Providing <b>1.5 TON 5 star Split AC system of Inverter type</b> along with indoor & outdoor units. The condenser shall be of Copper. Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) with copper condenser. Specify: Make : Model No. :	32	Nos.		
3	Providing <b>1 TON Split 5 Star AC system of Inverter type</b> along with indoor & outdoor units. The condenser shall be of Copper. Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) with copper condenser. Specify: Make : Model No. :	4	Nos.		
4	Providing <b>2 TON CASSETTE AC system (Single star or higher) of Inverter type</b> along with indoor & outdoor units. The condenser shall be of Copper. Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) with copper condenser.Specify: Make : Model No. :	7	Nos.		
<b>SUB TOTAL(A)</b>					<b>0.00</b>
		<b>SGST</b>	<b>14%</b>		0.00
		<b>CGST</b>	<b>14%</b>		0.00
		<b>TOTAL</b>			0.00
<b>LOW SIDE WORKS(B)</b>					
<b>S No.</b>	<b>Work Description</b>	<b>Qty</b>	<b>UOM</b>	<b>Rate</b>	<b>Amount</b>
6	Installing, testing and commissioning of <b>2 TR Split AC system</b> along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	18	Nos.		
7	Installing, testing and commissioning of <b>1.5 TR Split AC system</b> along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	32	Nos.		
8	Installing, testing and commissioning of <b>1 TR Split AC system</b> along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	4	Nos.		
9	Installing, testing and commissioning of <b>2 TON CASSETTE AC system</b> along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	7	Nos.		
11	Providing & fixing interconnected main 1.1 KV, multi stand, FRLS 4 Core x 2.5 Sq.mm (for 2Ton Split/cassette AC) wire & other accessories as per site requirement to complete the job in all respect. (Make: - Finolex/havells/Polycab)	310	mtr		
12	Providing & fixing interconnected main 1.1 KV, multi stand, FRLS 4 Core x 1.5 Sq.mm (for 1.5TON/1 TON Split AC) wire & other accessories as per site requirement to complete the job in all respect. (Make: - Finolex/havells/Polycab)	300	mtr		
13	Annealed temper copper pipe 5/8" & 3/8" with 13 mm nitrile rubber insulation etc for <b>2 Tr Split/2 tr cassette AC</b> (Make Totaline/Rajco/Mazflow)	220	mtr		
14	Annealed temper copper pipe 1/2" & 1/4" with 13 mm nitrile rubber insulation etc for <b>1.5 Tr/1.0 Split AC</b> (Make Totaline/Rajco/Mazflow)	250	mtr		
15	Supply & installation of UPVC Drain pipe (30mm)	350	mtr		
16	<b>Basic Stand</b> : Supply & installation of standard powder coated stand for AC outdoor unit.	61	Nos.		
18	Electronic Timer for auto switch on/off to AC of server/ATM/E-lobby for 4Hr/8Hr. Make:- Legrand, L&T. <b>(ATM ONLY)</b>	6	Nos.		
21	Removal of old Air conditioners along with refrigerant piping & stands.	61	Nos.		
<b>SUB TOTAL(B)</b>					<b>0.00</b>
		<b>SGST</b>	<b>9%</b>		0.00
		<b>CGST</b>	<b>9%</b>		0.00
		<b>TOTAL</b>			0.00
<b>TOTAL BASIC(A+B)</b>					<b>0.00</b>
<b>TOTAL INCL GST</b>					<b>0.00</b>