



BANK OF MAHARASHTRA
LOKMANGAL, 1501,
SHIVAJINAGAR, PUNE-411 005.

REVISED FINANCIAL BID

REVISION DATE: 31.08.2024

TENDER NO. AX1/CSD/TENDER/23/2024-25

TENDER DOCUMENT FOR "RATE CONTRACT FOR SUPPLY & INSTALLATION OF AIRCONDITIONERS FOR BRANCHES & PREMISES OF BANK OF MAHARASHTRA (PAN INDIA)."



PRICE BID : RATE CONTRACT FOR SUPPLY & INSTALLATION OF AIRCONDITIONERS FOR BRANCHES & PREMISES OF BANK OF MAHARASHTRA (PAN INDIA)

NOTE:

1. The Price Bid shall cover all clauses of the technical specifications and Detailed scope of work as per the tender.
2. QRO: Quoted rate only. QRO will not be considered for the evaluation of L1 Bidder.
3. Successful L1 Bidder will be the Bidder who has quoted maximum number of L1 rates of the Price Bid among the total technically qualified bidders. Subsequent L2, L3 Bidder will be based on descending number of L1 rates of the price bid. However, successful L1 bidder has to accept the all L1 rates of the line items where his quoted rates are not L1 rates.
4. All the quoted rates shall be exclusive of GST. GST will be in addition to the rate as applicable.

S No.	Work Description	Qty	UOM	Rate	Amount
HIGH SIDE WORKS(A)					
1	Providing 1 TON Split 5 Star AC system of Inverter type along with indoor & outdoor units. The condenser shall be of Copper.(Voltas/LG/Blue star/Daikin/Carrier/- (inverter units). Specify: Make : Model No. :	1	Nos.		
2	Providing 1.5 TON 5 star Split AC system of Inverter type along with indoor & outdoor units. The condenser shall be of Copper. (Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) . Specify: Make : Model No. :	1	Nos.		
3	Providing 02 TON Split 5 Star AC system of Inverter type along with indoor & outdoor units. The condenser shall be of Copper. (Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) Specify: Make : Model No. :	1	Nos.		
4	Providing 1.5 TON CASSETTE AC system (3 star or higher) of Inverter type along with indoor & outdoor units. The condenser shall be of Copper.(Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) Specify: Make : Model No.	1	Nos.		
5	Providing 02 TON CASSETTE AC system (3 star or higher) of Inverter type along with indoor & outdoor units. The condenser shall be of Copper.(Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) Specify: Make : Model No. :	1	Nos.		
6	Providing 03 TON CASSETTE AC system (3 star or higher) of Inverter type along with indoor & outdoor units. The condenser shall be of Copper.(Voltas/LG/Blue star/Daikin/Carrier/- (inverter units).Specify: Make : Model No. :	1	Nos.		
7	Providing 1 TON Window AC 5 Star AC system of Inverter type along with indoor & outdoor units. The condenser shall be of Copper.(Voltas/LG/Blue star/Daikin/Carrier/- (inverter units). Specify: Make : Model No. : QRO: Quoted rate only	1	Nos.	(QRO)	
8	Providing 1.5 TON Window AC 5 Star AC system of Inverter type along with indoor & outdoor units. The condenser shall be of Copper.(Voltas/LG/Blue star/Daikin/Carrier/- (inverter units). Specify: Make : Model No. : QRO: Quoted rate only	1	Nos.	(QRO)	
9	Providing 02 TON Window AC 3 Star AC system of Inverter type along with indoor & outdoor units. The condenser shall be of Copper.(Voltas/LG/Blue star/Daikin/Carrier/- (inverter units). Specify: Make : Model No. : QRO: Quoted rate only	1	Nos.	(QRO)	



LOW SIDE WORKS(B)					
S No.	Work Description	Qty	UOM	Rate	Amount
10	Installing, testing and commissioning of 1 TR Split AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	1	Nos.		
11	Installing, testing and commissioning of 1.5 TR Split AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	1	Nos.		
12	Installing, testing and commissioning of 2 TR Split AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	1	Nos.		
13	Installing, testing and commissioning of 1.5 TR CASSETTE AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	1	Nos.		
14	Installing, testing and commissioning of 02 TR CASSETTE AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	1	Nos.		
15	Installing, testing and commissioning of 03 TR CASSETTE AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	1	Nos.		
16	Providing & fixing interconnected main 1.1 KV, multi stand, FRLS 4 Core x 2.5 Sq.mm (for 2Ton Split/cassette AC) wire & other accessories as per site requirement to complete the job in all respect. (Make: - Finolex/ havells/Polycab)	1	mtr		
17	Providing & fixing interconnected main 1.1 KV, multi stand, FRLS 4 Core x 1.5 Sq.mm (for 1.5TON/1 TON Split AC) wire & other accessories as per site requirement to complete the job in all respect. (Make: - Finolex/ havells/Polycab)	1	mtr		
18	Annealed temper copper pipe 5/8'' & 3/8'' with 13 mm nitrile rubber insulation etc for 2 Tr Split/2 tr cassette AC (Make Totaline/Rajco/Mazflow)	1	mtr		
19	Annealed temper copper pipe 1/2'' & 1/4'' with 13 mm nitrile rubber insulation etc for 1.5 Tr/1.0 Split AC (Make Totaline/Rajco/Mazflow)	1	mtr		
20	Supply & installation of UPVC Drain pipe (30mm)	1	mtr		
21	Basic Stand : Supply & installation of standard powder coated stand for AC outdoor unit.	1	Nos.		
22	MS Stand/Platform: Providing & installing MS fabricated stand of angle 35mmx35mmx5mm in frame & 02 support railings and balance area shall be covered with 12mmx5mm MS flat with 4''c/c. The size of stand shall be sufficient to carry outdoor AC unit and additional space for technician to carryout maintenance. The stand shall be painted with synthetic enamel as directed by Bank.(For First Floor & above premises only)	1	Nos.		
23	Electronic Timer for auto swith on/off to AC of server/ATM/E-lobby for 4Hr/8Hr. Make:- Legrand, L&T. (ATM ONLY)	1	Nos.		
24	Removal of old Airconditioners along with refrigerant piping & stands.	1	Nos.		
25	Providing & fixing of 3 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 1Tr AC) Make: Microtek, V-Guards (Voltage Range 150- 280 Volts).	1	Nos.		



S No.	Work Description	Qty	UOM	Rate	Amount
26	Providing & fixing of 4 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 1.5Tr AC) Make: Microtek, V-Guards (Voltage Range 150- 280 Volts).	1	Nos.		
27	Providing & fixing of 5 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 02 Tr AC) Make: Microtek, V-Guards (Voltage Range 150- 280 Volts).	1	Nos.		
28	Installing, testing and commissioning of 01 TR Window AC system along with gas filling and ready to use condition. QRO: Quoted rate only	1	Nos.	(QRO)	
29	Installing, testing and commissioning of 1.5 TR Window AC system along with gas filling and ready to use condition. QRO: Quoted rate only	1	Nos.	(QRO)	
30	Installing, testing and commissioning of 02 TR Window AC system along with gas filling and ready to use condition. QRO: Quoted rate only	1	Nos.	(QRO)	

(Signature of the authorized person with stamp of the firm/company)

Name of the authorized person:

Date:

Declaration by Bidder:

I/We M/s..... have read & understood all the terms and conditions of tender, have acquainted to the site conditions and considering aforesaid and prevailing market conditions have quoted rate in price Bids.

SEAL & SIGN OF CONTRACTOR

