



बैंक ऑफ महाराष्ट्र
Bank of Maharashtra
भारत सरकार का उद्यम
एक परिवार एक बैंक

PRICE BID

**TENDER FOR SUPPLY, INSTALLATION, TESTING COMMISSIONING & MAINTENANCE
OF AIRCONDITIONERS AT RAIPUR ZONE BANK OF MAHARASHTRA**

AX49/GAD/TENDER/AC/RAIPUR ZONE/2023-24

Dated: 20.01.2024

12. PRICE BID

PRICE BID : SUPPLY, INSTALLATION, TESTING COMMISSIONING & MAINTENANCE OF AIRCONDITIONERS AT ZONE BANK OF MAHARASHTRA					
S No.	Work Description	Qty	UOM	Rate	Amount
HIGH SIDE WORKS(A)					
1	Providing 2 TON Split 3 Star AC system of Inverter type along with indoor & outdoor units. The condenser shall be of Copper. Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) with copper condenser.Specify: Make : Model No. :	6	Nos.		
2	Providing 1.5 TON 5 star Split AC system of Inverter type along with indoor & outdoor units. The condenser shall be of Copper. Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) with copper condenser. Specify: Make : Model No. :	12	Nos.		
3	Providing 1 TON Split 5 Star AC system of Inverter type along with indoor & outdoor units. The condenser shall be of Copper. Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) with copper condenser. Specify: Make : Model No. :	5	Nos.		
4	Providing 2 TON CASSETTE AC system(3 star or higher) of Inverter type along with indoor & outdoor units. The condenser shall be of Copper. Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) with copper condenser. Specify: Make : Model No. :	0	Nos.		
5	Providing 1.5 TON CASSETTE AC system (3 star or higher) of Inverter type along with indoor & outdoor units. The condenser shall be of Copper. Voltas/LG/Blue star/Daikin/Carrier/- (inverter units) with copper condenser. Specify: Make : Model No. :	0	Nos.		
SUB TOTAL(A)					0
		SGST	14%		0
		CGST	14%		0
		TOTAL			0
LOW SIDE WORKS(B)					
S No.	Work Description	Qty	UOM	Rate	Amount
6	Installing, testing and commissioning of 2 TR Split AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	6	Nos.		
7	Installing, testing and commissioning of 1.5 TR Split AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	12	Nos.		
8	Installing, testing and commissioning of 1 TR Split AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	5	Nos.		
9	Installing, testing and commissioning of 2 TON CASSETTE AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	0	Nos.		
10	Installing, testing and commissioning of 1.5 TON CASSETTE AC system along with gas filling and ready to use condition along with 3mtr Cu piping as supplied by OEM.	0	Nos.		
11	Providing & fixing interconnected main 1.1 KV, multi stand, FRLS 4 Core x 2.5 Sq.mm (for 2Ton Split/cassette AC) wire & other accessories as per site requirement to complete the job in all respect. (Make: - Finolex/havells/Polycab)	100	mtr		

TENDER NO:

AX49/GAD/TENDER/AC/RAIPUR ZONE/2023-24 Page 2 of 3

SEAL SIGN BIDDER

PRICE BID : SUPPLY, INSTALLATION, TESTING COMMISSIONING & MAINTENANCE OF AIRCONDITIONERS AT ZONE BANK OF MAHARASHTRA					
S No.	Work Description	Qty	UOM	Rate	Amount
12	Providing & fixing interconnected main 1.1 KV, multi stand, FRLS 4 Core x 1.5 Sq.mm (for 1.5TON/1 TON Split AC) wire & other accessories as per site requirement to complete the job in all respect. (Make: - Finolex/havells/Polycab)	200	mtr		
13	Annealed temper copper pipe 5/8" & 3/8" with 13 mm nitrile rubber insulation etc for 2 Tr Split/2 tr cassette AC (Make Totaline/Rajco/Mazflow)	100	mtr		
14	Annealed temper copper pipe 1/2" & 1/4" with 13 mm nitrile rubber insulation etc for 1.5 Tr/1.0 Split AC (Make Totaline/Rajco/Mazflow)	200	mtr		
15	Supply & installation of UPVC Drain pipe (30mm)	175	mtr		
16	Basic Stand : Supply & installation of standard powder coated stand for AC outdoor unit.	23	Nos.		
17	MS Stand/Platform : Providing & installing MS fabricated stand of angle 35mmx35mmx5mm in frame & 02 support railings and balance area shall be covered with 12mmx5mm MS flat with 4" c/c. The size of stand shall be sufficient to carry outdoor AC unit and additional space for technician to carryout maintenance. The stand shall be painted with synthetic enamel as directed by Bank.(For First Floor & above premises only)	0	Nos.		
18	Electronic Timer for auto switch on/off to AC of server/ATM/E-lobby for 4Hr/8Hr. Make:- Legrand, L&T. (ATM ONLY)	0	Nos.		
19	Providing & fixing of 4 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 1Tr /1.5Tr Split AC & 1.5 Tr Cassette AC) Make: Microtek, V-Guards (Voltage Range 150- 280 Volts). (RURAL BRANCHES ONLY)	0	Nos.		
20	Providing & fixing of 5 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 02 Tr Split AC & 02 Tr Cassette AC) Make: Microtek, V-Guards (Voltage Range 150- 280 Volts). (RURAL BRANCHES ONLY)	2	Nos.		
21	Removal of old Airconditioners along with refrigerant piping & stands.	23	Nos.		
SUB TOTAL(B)					0
		SGST	9%		0
		CGST	9%		0
		TOTAL			0
TOTAL BASIC(A+B)					0
TOTAL INCL GST					0

Declaration by Bidder:

I/We M/s..... have read & understood all the terms and conditions of tender, have acquainted to the site conditions and considering aforesaid and prevailing market conditions have quoted rate in price Bids.

TENDER NO:

AX49/GAD/TENDER/AC/RAIPUR ZONE/2023-24 Page 3 of 3

SEAL SIGN BIDDER