

**SPECIFICATIONS AND BOQ FOR THE PROPOSED INTERIOR WORK TO BE EXECUTED AT
BANK OF MAHARASHTRA, HYDERABAD ZONAL OFFICE & SULTAN BAZAR BRANCH , HYDERABAD.**

GENERAL INSTRUCTION TO THE CONTRACTOR

THE CONTRACTOR SHALL STRICTLY ADHERE TO THE FOLLOWING INSTRUCTIONS UNLESS MENTIONED IN THE BOQ.

- 1 19mm Plywood to be used for all table tops, verticals, key board slider, draw sides. / 12mm for the modesty panel , in case of curvatures 2 nos 6mm Flexible plywood to be used.
- 2 All table tops with 1.5mm thick Laminate, All vertical and exposed outside and all internal visible surface of the plywood, all inside the doors , shelves tops, all internal area of drawer should be covered with 1mm thick Laminate.
- 3 All the storage units and flap doors should be fixed with Box hinges and Key board slider should slide on Telescopic channels only.
- 4 The design patterns / drawing indicated in the tender are tentative only and The final patterns and shades / colours should be as per the instructions of the Architect / Bank authority.
- 5 All tables/ counters should be provided with CPU stand for keeping CPU below the counter .
- 6 Foot rest of 2"x3" teak wood should be provided for all the tables and counters with duly polished finish.
- 7 All the exposed edges of plywood / partitions / doors must be covered with 12mm thick and respective thickness Steam beech wood ripper as per design and duly
- 8 Any discrepancy in the site conditions / measurements in the drawings shall be brought to the notice of the Architects office.
- 9 For Round / Curve shaped counters / tables the measurement will be taken in the center of the top width for billing purpose.
- 10 Cost of Taps / plumbing / drainage should be included with all the fitting given in the tender , No separate claim will be allowed for this.
- 11 Contractor should work keeping running banks time in mind and bank authority decision will be final on the timings.
- 12 As the Branch is in working form, the work to be done should be in phases and should cooperate other agencies working.
- 13 Cable managers should be provided wherever required by the bank.
- 14 Contractor Should not object for any deduction in the items of said work.

APPROVED BRANDS / MAKES	
A	PLYWOOD <u>BWP 710 GRADE ISI</u> : AUSTIN, CENTURY, GREENPLY, MAYUR. (Subsidiary Brand of these Companies like Green Ecotech / Century Sainik are NOT Allowed)
B	LAMINATE : ROYAL TOUCH , FORMICA , GREENLAM. ::: NATURAL VENEER : TRUWOOD, DURO, NATURAL, TIMEX,CENTURY.
C	MDF BOARD - GRADE-II , IS 12406 of 2003 : NUWUD , DURATUFF.
D	LOCKS : GODREJ, EBCO, DOOSET for Doors , Storages.
E	CHANELS : EBCO (Telescopic Cromium Plated), HETTICH.
F	MAIN DOOR / DOOR / STORAGE DOOR HANDLES: DORSET , KITCH, GODREJ
G	DOOR CLOSER/ FLOOR SPRING/ PATCH FITTINGS : DORMA, GODREJ.
H	GYPSUM BOARD: INDIA GYPSUM , BORAL PASTER BOARD.
I	24"X24" GRID CEILING BOARD: ARMSTRONG, CIPRO, NITTIBO.
J	GLASS : MODI FLOAT, SAINT GOBAIN.
K	VERTICAL BLINDS (WITH SCOTCH GUARD): VISTA ,MAC, HUNTER DOUGLAS,
L	WALL PAINTS: ICI VELVET TOUCH , ASIAN ROYALE EMULSION.
M	TEXTURE (Exteriors and Interiors): SPECTRUM , WALL TEXTURES.
N	ROLLER TEXTURE: ICI DUET, BURGER PAINTS.
O	WOODEN FRAME/ BEADING: STEAM BEECH WOOD.
P	VETRIFIED TILES 24"X24": RAK CERAMICS, VARMORA, ASIAN.
Q	GROUTING/ADHESIVE FOR VETRIFIED TILES: LATICRATE, FOSROCK.
R	CERAMIC FLOOR / WALL TILES ; JOHNSON, KAJARIA, SOMANY.
S	TOILET FITTINGS: CERAWARE, HINDWARE, PARRY WARE.
T	TAP FITTINGS: ESS ESS , MARC, PARRY WARE.
U	FOAM : KING FOAM.
V	UPHOLSTRY: HARMONY
W	CHAIRS: GODREJ, GARNIER.

I ZONAL OFFICE					
S.N.	DESCRIPTION	QNTTY	UNIT	RATE	AMOUNT
A	INTERIOR WORK				
1	Entrance partitions and Door : Providing & Fixing of Entrance Partition with Door all made with 12 mm Toughened Glass and Patch fittings. Glass should be Etching (Acid work) design. Two Doors should be Heavy Duty Floor spring and 18" SS satin finish Handles. Dead lock at the floor level to be fixed to both the doors. Patch fittings of Dorma / Godrej / Ozone make, as per the instructions / approval from engineer in charge or consultant, all inclusive of labour, material etc.	106	Sqft		
2	Full Height Solid Partitions : Providing and Fixing of Full height partitions all made with MDF frame work of 2.5"x 35mm section with 2'0"x2'0" c/c vertically and horizontally(incase of non availability of 35mm thick MDF, this section should be made by using two layers of 18mm thick MDF X2.5" to make 2.5"x36mm in size). Frame to be covered with 6mm plywood from both sides. 1mm thick laminate to be covered from both the sides of the partition. Frame should be properly fixed to the Floor , Vertical members should be firmly to the Slab and side wall available. Laminate should be considered in two colour combination. All as per the design and instructions of the design in charge.(measurements upto false celing level only and Excluding doors area)	1050	Sqft		
3	Full Height Semi Glazed Partitions : Same as Item no 3 but 8mm Plain Glass with Etching & Acid texture DESIGN Should be provided with 35mm x 12mm Steam beach Molding duly melamine polished. This glass will be starting from 2'6" ht from ffl .All as per the design and instructions of the design in charge.	745	Sqft		
4	Low Ht /Half Ht Semi Glazed Partitions : Same as Item no 3 but Low ht or Half height as per design But 12mm glass instead of 8mm glass with edges polished to be used . All other specs same as item no 2, Edges of the partition to be covered with 4"x1.5" Steam beach wood duly malemine polished moulding. All as per the design and instructions of the design in charge.	1550	Sqft		
5	Low Ht /Half Ht Solid Partitions : Same as Item no 3 but Low ht or Half height as per design .Edges of the partition to be covered with 4"x1.5" Steam beach wood duly malemine polished moulding. All as per the design and instructions of the design in charge.	275	Sqft		

6	Full Height Fully GLAZED Partitions including Doors : Providing and Fixing of Full height Fully Glazed partitions all made with 12mm thick <u>Toughened Glass</u> and <u>patch fittings</u> , 12mm glass to be fixed to floor with Patch Fittings. MDF frame work of 2.5"x 35mm section with 2'0"x2'0" c/c vertically and horizontally(incase of non availability of 35mm thick MDF, this section should be made by using two layers of 18mm thick MDF X2.5" to make 2.5"x36mm in size). Frame should be properly fixed to the Slab. This frame should Act as the Support for 12mm toughned glass at Flase Ceiling Level. This Frame should be Hidden below the Faslce Ceiling. All as per the design and instructions of the design in charge.(measurements upto false celing level only)	430	Sqft		
7	Column / Wall Paneling / Rolling Shutter box : Providing and Fixing of Wall Paneling made with 1.5"x1.5" M Teak wood Frame work Properly fixed to the Wall or Column with proper Spirit / Plumb level. Frame work to be covered with 6mm thick Plywood and 1mm thick Laminate in two colour combination . All as per the design and instructions of the design in charge.	1650	Sqft		
8	Semi Glazed Door : Doors All made in 35mm thick Flush door with 1mm lamination form both sides and 8mm plain glass with Etching / Acid texture border fixed with Steam beach molding duly melamine polished. 35mmX 12mm steam beach Lipping to be provided to all the edges of the door . Rate also to include the cost of Door Frame made with 3.5" X 1.5" Steam beach wood. Door Frame should be fixed properly to the Partitions, All Hardware should be of Brass / SS Brush finish with ISI mark. Hardware includes Concealed Door closer, Cylindrical Lock, Door stopper and other standard needs . All as per design and instructions of the design incharge.	63	Sqft		
9	Solid Doors : Same as Item no.7 but the Door Frame should of Teak wood of 4.5"x2.5" section and No Glass.	210	Sqft		
10	Gypsum Board False Ceiling : Providing and Fixing Main Frame Suspended ceiling consisting of fixing company made GI chanel of 27mm X 0.5 mm thick having one flange of 20mm and another flange of 30mm along with perimeter of the ceiling. Frame should be properly anchored to the Slab . The suspending GI intermediet chanel of size 45mm x 0.55 mm thick with two flanges of each from the soffit @1200 mm centers with GI hangers of 25mm x 0.5mm thick fixed to soffit with GI cleat and steel expansion Anchor fasteners and to intermediet chanel with GI nut and bolt. Ceiling section of 0.5mm thickness having knurled wedge of 51.5 mm and flanges of 26mm each with clips of 10.5mm fixed to the int. chanel with help of connecting clips in perpendicular direction to the intermeiate chanel at 450mm center, 12.5mm thick tapered Edge Gypsum plaster board is to be fixed with 25mm screws maintaining proper distance . Surface to be finished with tape and plaster. Cost to include the cutout provision for AC Grill, Light Fittings and any other gazetts as per requirement. (Chanel and Board should be of Saint Gobain Make)	3600	Sqft		

11	24"x24" Grid False Ceiling (SILHOUTE GRID AND DUNE Premier Micro Look): Providing and Fixing False ceiling Grid using hot dipped Galvonised steel sections, exposed surface chemically cleaned capping prefinished in baked polyster paint. Main tee of size 3000 x 32 x 24 mm at every 1200mm c/c maximum, 1200mm cross Tee of size 1200 x 27 x 24mm at every 600mm intervals and 600 mm cross Tee of size 600 x 25 x 24mm at every 1200mm max and 3000 x 19 x 19mm wall angle all around the wall to form grid size of 600mm x 600mm . The Main grid to be suspended to the MS frame with 2mm pre-straightened GI wire and GI adjustable clamp and Laying of Dune premier micro look mineral fiber tiles / board having Fire rating of 60 min. as per BS 476/23 of 1987 , Noise reduction co-eff. (NRC) of 0.50, Light reflectance of 83%, Sound atteneuation of 32db, thermal conductivity of k=0.052 W/m, wt of 4kgs/mts and humidity resistance of RH-95 , with paint finish of 600x600mm x 12mm thick over the Grid.All as per the design and instructions of the design incharge.	3000	Sqft		
13	Walls and Gypsum ceiling paint finish: Walls / Gypsum Ceiling with the Base with POP Punning to plumb level and 2 to 3 coats of Royel Shine emulsion on 2 to 3 coats of white cement base putty finish (Birla Wall care / JK White cement putty) and one coat of primer afterputy finish. All as per the instructions of the design in charge.				
	a. Walls (Putty and paint)	150	Sqft		
	b. False ceiling (Putty and paint)	3000	Sqft		
14	Roller Texture Paint :(Royal play of Asian Make or equivalent) Duet Roller texture Paint with lacquer coating as per the required colour combination after proper surface preperation.All as per the instructions of the design in charge.	Rate Only	Sqft		
15	Wall Paper : Supply and Fixing A grade Vinyl washable Wall Paper on properly required wall surface.All as per the instructions of the design in charge.(basic rate Rs 100/- sqft)	Rate Only	Sqft		
16	Roller Blinds : Roller Blinds of thick fabric as per specification and brand. All as per the instructions of the design in charge. Hunter Douglas / Touch make	525	Sqft		
		SUB TOTAL A			

B	FURNITURE WORK				
19	<p>DGM's Table : Managers Table overall size 8'0"x3'6" with Two pedestals. 19mm thick plywood for Top and for pedestals . Top should be shown double thickness at the edges. 12mm plywood for modesty panel.8 / 9 mm for drawer bottom. Table top should be of Italian Marble of Crema Flora Variety (Rs 275/- to 300/- per Sqft base cost) to be fixed on 19mm plywood base, Marble duly polished with 3M Tin Oxide Polish with Edges Double moulded. 4 mm thick natural veneer (Base rate 120/- sqft) duly malemine polished for all the exposed surfaces and 1mm thick laminate for all internal visible and non visible areaarea of plywood . All the surfaces of the draws internally and externally should be covered with 1mm thick laminate.All the draws and key board tray should slide on telescopic chanel. All handles of Brush finished SS handles , Strap lock , Box hinges etc standerd hardware.All the Exposed Edges of Plywood should be covered with 12mm thick plain Steam beech beading duly malemine polished. Cable manager provsion to be provided in the table top even in glass. All as per the design and the instructions of the design incharge.</p>	1	no		
20	<p>DGM's Side Runner / Credenza : Side table of size 4'0"x2'6"x21"deep . 19mm ply for all horizontal and verticals. One Key board tray made with 19mm plywood and 1mm lamination for all inside surfaces , sliding on telescopic chanel. Two Flap door below the Key board tray. 9mm thick for the back side of the side table to be fixed. All exposed areas including back side should be covered with 1mm thick laminate and 4mm thick veneer for the Top.12mm Glass to be provided and fixed with the help of 6" ht SS studs as Top. All Hardware matching to the Table. All as per the design and the instructions of the design in charge.</p>	1	no		
21	<p>Back Rack in DGM's Cabin: All as per the Design made in 19mm and 9mm plywood with 4mm veneer with malemine ploish finish for all Exposed and 1mm thick laminate for Internal surface of the Plywood. Bottom part up to 2'6" ht will be of 21" deep and remaining ht up to 7'0" will be 16"deep. 8mm glass with etching / acid texture doors should be provided at 16" deep unit with Steam beech wood frame work of 3"x1.5" section duly melamine polished. All the Shelves behind glass doors should be of 12mm thick flat edge polished fixed in SS D brackets. All other Hardware should be matching to table and side table. All as per the design and the instructions of the design in charge.</p>	66	Sqft		

22	Wall Paneling in DGM Cabin: Providing and Fixing of Wall Paneling made with 1.5"x1.5" M Teak wood Frame work Properly fixed to the Wall or Column with proper Spirit / Plumb level. Frame work to be covered with 6mm thick Plywood and 4 mm thick natural veneer (Base rate 120/- sqft) duly malemine polished for all the exposed surfaces . All as per the design and instructions of the design in charge	90	Sqft		
23	AGM's Tables : AGM Table overall size 7'x2'6" with Single draw pedestals. 19mm thick plywood for Top and for padestals . Top should be shhown double thickness at the edges. 12mm plywood for modesty panel. 6mm for drawer bottom. Table top should be of Italian Marble of Crema Flora Variety (Rs 275/- to 300/- per Sqft base cost) to be fixed on 19mm plywood base, Marble duly polsid=hed with 3M Tin Oxide Polish with Edges Double moulded. 1.5 mm thick laminate for the top. 1mm thick laminate for all the exposed surfaces and all intrnal visible area of plywood . All the surfaces of the draws internally and externally should be covered with 1mm thick laminate.All the draws and key board tray should slide on telescopic chanel. All handles of Brush finished SS handles , Strap lock , Box hinges etc standerd hardware.All the Exposed Edges of Plywood should covered with 12mm thick plain Steam beech beading duly malemine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly malemine polished. 6mm thick plain glass with bevelled egdes Table top should be provided.Cable manager provsion to be provided in the table top even in glass. All as per the design and the instructions of the design incharge.	2	nos		
23	Chief Manager Tables : Officer Table overall size 6'x2'3" with Single draw pedestals. 19mm thick plywood for Top and for padestals . Top should be shhown double thickness at the edges. 12mm plywood for modesty panel. 6mm for drawer bottom. 1.5 mm thick laminate for the top. 1mm thick laminate for all the exposed surfaces and all intrnal visible area of plywood . All the surfaces of the draws internally and externally should be covered with 1mm thick laminate.All the draws and key board tray should slide on telescopic chanel. All handles of Brush finished SS handles , Strap lock , Box hinges etc standerd hardware.All the Exposed Edges of Plywood should covered with 12mm thick plain Steam beech beading duly malemine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly malemine polished. 6mm thick plain glass with bevelled egdes Table top should be provided.Cable manager provsion to be provided in the table top even in glass. All as per the design and the instructions of the design incharge.	3	nos		

24	<p>Sr Managers Tables : Officer Table overall size 5'0"x2'3" with Single draw pedestals. 19mm thick plywood for Top and for pedestals . Top should be shown double thickness at the edges. 12mm plywood for modesty panel. 6mm for drawer bottom. 1.5 mm thick laminate for the top. 1mm thick laminate for all the exposed surfaces and all intrnal visible area of plywood . All the surfaces of the draws internally and externally should be covered with 1mm thick laminate.All the draws and key board tray should slide on telescopic chanel. All handles of Brush finished SS handles , Strap lock , Box hinges etc standerd hardware.All the Exposed Edges of Plywood should covered with 12mm thick plain Steam beech beading duly malemine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly malemine polished. 6mm thick plain glass with bevelled egdes Table top should be provided.Cable manager provsion to be provided in the table top even in glass. All as per the design and the instructions of the design incharge.</p>	8 nos			
24	<p>Managers / Officers Tables : Officer Table overall size 4'6"x2'3" with Single draw pedestals. 19mm thick plywood for Top and for pedestals . Top should be shown double thickness at the edges. 12mm plywood for modesty panel. 6mm for drawer bottom. 1.5 mm thick laminate for the top. 1mm thick laminate for all the exposed surfaces and all intrnal visible area of plywood . All the surfaces of the draws internally and externally should be covered with 1mm thick laminate.All the draws and key board tray should slide on telescopic chanel. All handles of Brush finished SS handles , Strap lock , Box hinges etc standerd hardware.All the Exposed Edges of Plywood should covered with 12mm thick plain Steam beech beading duly malemine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly malemine polished. 6mm thick plain glass with bevelled egdes Table top should be provided.Cable manager provsion to be provided in the table top even in glass. All as per the design and the instructions of the design incharge.</p>	16 nos			
25	<p>Side Tables / Credenzas : Side table of size 3'6"x2'3"x18"deep . 19mm ply for all horizontal and verticals. Two draws made with 19mm plywood and 1mm lamination sliding on telescopic chanel. Two Flap door below the Drawers. 9mm thick for the back side of the side table to be fixed. All exposed areas including back side should be covered with 1mm thick laminate and 1.5mm thick laminate for the Top. All Hardware matching to the Table. All as per the design and the instructions of the design in charge.</p>	30 nos			

26	<p>Back Racks for AGM / CM / Sr. Mangrs /Officers: All as per the Design made in 19mm and 9mm plywood with 1mm thick laminate for all Exposed as well as Internal surface of the Plywood. Bottom part up to 2'6" ht will be of 21" deep and remaining ht up to 7'0" will be 16"deep. 8mm glass with etching / acid texture doors should be provided at 16" deep unit with Steam beech wood frame work of 3"x1.5" section duly melamine polished. All the Shelves behind glass doors should be of 12mm thick flat edge polished fixed in SS D brackets. All other Hardware should be matching to table and side table. All as per the design and the instructions of the design in charge.</p>	575	Sqft		
27	<p>Clerical Tables (Work Stations) : Clerical Table overall size 4'9"x2'0" / 4'6"x2'0" with Single pedestal. 19mm thick plywood for Top and for padestals . Top should be shhown double thickness at the edges. 12mm plywood for modesty panel. 6mm for drawer bottom. 1.5 mm thick laminate for the top. 1mm thick laminate for all the exposed surfaces and all intrnal visible area of plywood . All the surfaces of the draws internally and externally should be covered with 1mm thick laminate.All the draws and key board tray should slide on telescopic chanel. All handles of Brush finished SS handles , Strap lock , Box hinges etc standerd hardware.All the Exposed Edges of Plywood should covered with 12mm thick plain Steam beech beading duly malemine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly malemine polished.Cable manager provsion to be provided in the table top. All as per the design and the instructions of the design incharge.</p>	32	Rft		
28	<p>EDP room table: Table top 2'0" wide . All made in 19mm plywood and 1mm laminate for all vertical and inside areas and 1.5 mm thick Laminate for the table top . Modesty panel should be at least 12mm thick. One Key board tray and One pedestal 16" wide containing 2 draws and one flap door to be provided at every 4'6". All made in 19mm plywood and 1mm thick laminate even for the internal areas of the plywood. all draws and key board tray should be on telescopic channel and other hardware items as specified. All the edges of the plywood to be covered with 12mm thick steam beech beading duly melamine polished. All as per design and instructions of the design in charge.</p>	19	Rft		

29	Low Height Storage Racks: Providing and installing of 18" deep storage racks , ht 2'6" / 4'0", length as per drg. All made in 19mm thick plywood and 9mm plywood for back side. All the Outside and Inside exposed surfaces of plywood to be with 1mm thick laminate and top with 1.5mm thick laminate. Inside bothsides 1mm laminated 19mm plywood loose shelves to be provided at every 15" gap. Vertical supports should not exceed 3'0" gap and each door shutter size should not exceed 18" in width and 3'6" in ht. All hardware should be as per specs. All exposed edges of plywood should be with 12mm thick Steam beach wood molding duly melamine polished. All as per the instructions.	350	Sqft		
30	Full height Storage Racks: Same as item above but the height may vary from 4'0" to 8'0". All as per the Instructions. This item is Addition after using existing Steel Almaras available	450	Sqft		
31	Mini Discussion room table: 24" Deep Table with Box type Base and 19 mm Top all with 1.5mm thick Laminate on top and 1mm lamiante for other surfaces, All the Exposed Edges of Plywood should covered with 12mm thick plain Steam beech beading duly malemine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly malemine polished. 6mm thick plain glass with bevelled egdes Table top should be provided. Cable manager provsion to be provided in the table top even in glass. All as per the design and the instructions of the design incharge.	18	rft		
32	Pantry Platform : 2'0" Deep x 9' wide all made with plywood , laminate, and Granite Table Top.all Storage below the Counter, all as per thr instructions of Design incharge.	9	Rft		
33	Pin Up Boards: Supply and Fixing of Soft board / pin up board made with 12mm thick soft board and F6mm foam and Fabric covering,,,	120	Sqft		
		SUB TOTAL B			
TOTAL AMOUNT : I (ZONAL OFFICE)				A+B	

II SULTAN BAZAR BRANCH					
S.N.	DESCRIPTION	QNTTY	UNIT	RATE	AMOUNT
C	INTERIOR WORK				
1	Facad of Entrance Door: Providing and fixing in position Aluminium composite panel Boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5mm-3mm-0.5mm) including fabrication for the same with aluminium sections, required hardware, silicon sealent (Dow Corning 789) masking tape, necessary scaffolding etc complete in all respects.	100	Sqft		
2	Full Height Solid Partitions : Providing and Fixing of Full height partitions all made with MDF frame work of 2.5"x 35mm section with 2'0"x2'0" c/c vertically and horizontally(incase of non availability of 35mm thick MDF, this section should be made by using two layers of 18mm thick MDF X2.5" to make 2.5"x36mm in size). Frame to be covered with 6mm plywood from both sides. 1mm thick laminate to be covered from both the sides of the partition. Frame should be properly fixed to the Floor , Vertical members should be firmly to the Slab and side wall available. Laminate should be considered in two colour combination. All as per the design and instructions of the design in charge.(measurements upto false ceiling level only and Excluding doors area)	475	Sqft		
3	Full Height Semi Glazed Partitions : Same as Item no 2 but 8mm Plain Glass with Etching & Acid texture DESIGN Should be provided with 35mm x 12mm Steam beach Molding duly melamine polished. This glass should start from 2'0" / 2'6" ht from ffl .All as per the design and instructions of the design in charge.	210	Sqft		
4	Low Ht /Half Ht Semi Glazed Partitions (4'6" or 7'0" Ht) : Same as Item no 2 but Low ht or Half height as per design But 12mm glass instead of 8mm glass with edges polished to be used with Etching & Acid texture DESIGN . All other specs same as item no 2, Edges of the partition to be covered with 4"x1.5" Steam beach wood duly malemine polished moulding. All as per the design and instructions of the design in charge.	510	Sqft		
4A	Low Ht /Half Ht Solid Partitions : Same as Item no 2 but Low ht or Half height as per design .Edges of the partition to be covered with 4"x1.5" Steam beach wood duly malemine polished moulding. All as per the design and instructions of the design in charge.	120	Sqft		

5	Full Height Fully GLAZED Partitions including Doors : Providing and Fixing of Full height Fully Glazed partitions all made with 12mm thick Toughened Glass and patch fittings, 12mm glass to be fixed to floor with Patch Fittings. The Rate Should be inclusive of MDF frame work of 2.5"x 35mm section with 2'0"x2'0" c/c vertically and horizontally(incase of non availability of 35mm thick MDF, this section should be made by using two layers of 18mm thick MDF X2.5" to make 2.5"x36mm in size). Frame should be properly fixed to the Slab. This frame should Act as the Support for 12mm toughned glass at Flase Ceiling Level. This Frame should be Hidden below the Fasle Ceiling. All as per the design and instructions of the design in charge.(measurements upto false celing level only)	Rate only	Sqft		
6	Column / Wall Paneling / Rolling Shutter box : Providing and Fixing of Wall Paneling made with 1.5"x1.5" MDF Frame work Properly fixed to the Wall or Column with proper Spirit level , 2'x2' grid frame. Frame work to be covered with 12 mm thick Plywood and 1mm thick Laminate in two colour combination . All as per the design and instructions of the design in charge.	975	Sqft		
7	Semi Glazed Door : Doors All made in 35mm thick Flush door with 1mm lamination form both sides and 8mm plain glass with Etching / Acid texture border fixed with Steam beach molding duly melamine polished. 35mmX 12mm steam beach Lipping to be provided to all the edges of the door . Rate also to include the cost of Door Frame made with 3.5" X 1.5" Steam beach wood. Door Frame should be fixed properly to the Partitions, All Hardware should be of Brass / SS Brush finish with ISI mark. Hardware includes Concealed Door closer, Cylindrical Lock, Door stopper and other standard needs . All as per design and instructions of the design incharge.	105	Sqft		
8	Solid Doors : Same as Item no.7 but the Door Frame should of Teak wood of 4.5"x2.5" section and No Glass.	42	Sqft		
9	Main Entrance Partitions / Door : All made with Toughened 12mm thick plain Glass with Etching / Acid texture Border fixed with Patch / Spider Fittings. Exposed edges of the Partition Glass should be Flat Polished. Door should be with TOUGHNED 12mm glass Patch Fitting / properly Hung on Heavy duty Floor spring. and with 15" Brush finished SS handle as specified. Frosted Flim of 3M make as per Design to be provided and Fixed. All as per the design and instructions of the design in charge.				
9a	Door	126	Sqft		
9b	Partitions (Fixed Glass)	320	Sqft		

10	Gypsum Board False Ceiling: (Using Existing Fixed GI Chnals) (Cost of GI Chnals to be Excluded in the Cost): Providing and Fixing Main Frame Suspended ceiling consisting of fixing company made GI chnals of 27mm X 0.5 mm thick having one flange of 20mm and another flange of 30mm along with perimeter of the ceiling. Frame should be properly anchored to the Slab . The suspending GI intermediat chnals of size 45mm x 0.55 mm thick with two flanges of each from the soffit @1200 mm centers with GI hangers of 25mm x 0.5mm thick fixed to soffit with GI cleat and steel expansion Anchor fasteners and to intermediat chanel with GI nut and bolt. Ceiling section of 0.5mm thickness having knurled wedge of 51.5 mm and flanges of 26mm each with clips of 10.5mm fixed to the int. chnals with help of connecting clips in perpendicular direction to the intermeiate chnals at 450mm center, 12.5mm thick tapered Edge Gypsum plaster board is to be fixed with 25mm screws maintaining proper distance . Surface to be finished with tape and plaster. Cost to include the cutout provision for AC Grill, Light Fittings and any other gazetts as per requirment.	1350	Sqft		
11	24"x24" Grid False Ceiling (SILHOLTE GRID): Providing and Fixing False ceiling Grid using hot dipped Galvonised steel sections, exposed surface chemically cleaned capping prefinished in baked polyster paint. Main tee of size 3000 x 32 x 24 mm at every 1200mm c/c maximum, 1200mm cross Tee of size 1200 x 27 x 24mm at every 600mm intervals and 600 mm cross Tee of size 600 x 25 x 24mm at every 1200mm max and 3000 x 19 x 19mm wall angle all around the wall to form grid size of 600mm x 600mm . The Main grid to be suspended to the MS frame with 2mm pre-straightened GI wire and GI adjustable clamp and Laying of fibre wool board having Fire rating of 60 min. as per BS 476/23 of 1987 , Noise reduction co-eff. (NRC) of 0.50, Light reflectance of 83%, Sound atteneuation of 32db, thermal conductivity of k=0.052 W/m, wt of 4kgs/mts and humidity resistance of RH-95 , with paint finish of 600x600mm x 12mm thick over the Grid.All as per the design and instructions of the design incharge.	1200	Sqft		
12	Plaster of Paris Cornices : Providing and Fixing of 4" to 6" wide Cornices as per the Given design in Plaster of Paris. All as per the design and instructions of the design in charge.	1	Rft		
13	Walls and Gypsum ceiling paint finish: Walls with the Base with POP Punning to plumb level and 2 to 3 coats of Plastic emulsion on 2 to 3 coats of lappam and 2 coats of primer one before and one after lappam. All as per the instructions of the design in charge.				

	a. Walls : (Lappam and paint) (Birla Wall Care and Asian Royale Shine)	150	Sqft		
	b. False ceiling (Lappam and paint) (Birla Wall Care and Asian Royale Shine)	1350	Sqft		
14	Texture Paint : Spectrum texture paint spray bubble type with proper surface preparation.All as per the instructions of the design in charge.	Rate only	Sqft		
15	Roller Texture Paint : Royal Play / Duet Roller texture Paint with lacquer coating as per the required colour combination after proper surface preparation.All as per the instructions of the design in charge.	Rate only	Sqft		
16	Vertical Roller Blinds : Roller Blinds WITH PVC fabric as per specification and brand. All as per the instructions of the design in charge. Stanadard make	260	Sqft		
		SUB TOTAL C			
D	FURNITURE WORK				
17	Branch Managers (AGM) Table : AGM Table overall size 7'6"x2'6" with Single draw pedestals. 19mm thick plywood for Top and for pedestals . Top should be shown double thickness at the edges. 12mm plywood for modesty panel. 6mm for drawer bottom. Table top should be of Italian Marble of Crema Flora Variety (Rs 275/- to 300/- per Sqft base cost) to be fixed on 19mm plywood base, Marble duly polsid=hed with 3M Tin Oxide Polish with Edges Double moulded. 1.5 mm thick laminate for the top. 1mm thick laminate for all the exposed surfaces and all intrnal visible area of plywood . All the surfaces of the draws internally and externally should be covered with 1mm thick laminate.All the draws and key board tray should slide on telescopic chanel. All handles of Brush finished SS handles , Strap lock , Box hinges etc standerd hardware.All the Exposed Edges of Plywood should covered with 12mm thick plain Steam beech beading duly malemine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly malemine polished. 6mm thick plain glass with bevelled egdes Table top should be provided.Cable manager provsion to be provided in the table top even in glass. All as per the design and the instructions of the design incharge.	1	no		
18	BM's (AGM) Side Table : Side table of size 4'0"x2'6"x21"deep . 19mm ply for all horizontal and verticals. One Key board tray made with 19mm plywood and 1mm lamination sliding on telescopic chanel. Two Flap door below the Key board tray. 9mm thick for the back side of the side table to be fixed. All exposed areas including back side should be covered with 1mm thick laminate . All Hardware matching to the Table. All as per the design and the instructions of the design in charge.	1	no		

19	Back Rack in BM's (AGM) Cabin: All as per the Design made in 19mm and 9mm plywood with 1mm thick laminate for Internal surface of the Plywood. Bottom part up to 2'6" ht will be of 21" deep and remaining ht up to 7'0" will be 16"deep. 8mm glass with etching / acid texture doors should be provided at 16" deep unit with Steam beech wood frame work of 3"x1.5" section duly melamine polished. All the Shelves behind glass doors should be of 12mm thick flat edge polished fixed in SS D brackets. All other Hardware should be matching to table and side table. All as per the design and the instructions of the design in charge.	38	Sqft		
20	Officer Tables : Officer Table overall size 5'6"x2'3" with Single draw pedestals. 19mm thick plywood for Top and for padestals . Top should be shhown double thickness at the edges. 12mm plywood for modesty panel. 6mm for drawer bottom. 1.5 mm thick laminate for the top. 1mm thick laminate for all the exposed surfaces and all intrnal visible area of plywood . All the surfaces of the draws internally and externally should be covered with 1mm thick laminate.All the draws and key board tray should slide on telescopic chanel. All handles of Brush finished SS handles , Strap lock , Box hinges etc standerd hardware.All the Exposed Edges of Plywood should covered with 12mm thick plain Steam beech beading duly malemine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly malemine polished. 6mm thick plain glass with bevelled egdes Table top should be provided.Cable manager provsion to be provided in the table top even in glass. All as per the design and the instructions of the design incharge.	3	nos		
21	Side Tables / Credenzas : Side table of size 3'6"x2'6"x18"deep . 19mm ply for all horizontal and verticals. Two draws made with 19mm plywood and 1mm lamination sliding on telescopic chanel. Two Flap door below the Drawers. 9mm thick for the back side of the side table to be fixed. All exposed areas including back side should be covered with 1mm thick laminate and 1.5mm thick laminate for the Top. All Hardware matching to the Table. All as per the design and the instructions of the design in charge.	9	nos		
22	Back Racks for officers: All as per the Design made in 19mm and 9mm plywood with 1mm thick laminate for all Exposed as well as Internal surface of the Plywood. Bottom part up to 2'6" ht will be of 21" deep All other Hardware should be matching to table and side table. All as per the design and the instructions of the design in charge.	120	Sqft		

<p>23</p>	<p>Clerical Tables / Work Stations for System Room / Daftary table etc : 2'0" wide Work stations with Single pedestal at every 4'0" . 19mm thick plywood for Top and for pedestals . Top should be shown double thickness at the edges. 12mm plywood for modesty panel. 6mm for drawer bottom. 1.5 mm thick laminate for the top. 1mm thick laminate for all the exposed surfaces and all intrnal visible area of plywood . All the surfaces of the draws internally and externally should be covered with 1mm thick laminate.All the draws and key board tray should slide on telescopic chanel. All handles of Brush finished SS handles , Strap lock , Box hinges etc stander hardware.All the Exposed Edges of Plywood should covered with 12mm thick plain Steam beech beading duly malemine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly malemine polished.Cable manager provsion to be provided in the table top. All as per the design and the instructions of the design incharge.</p>	<p>24</p>	<p>rft</p>		
<p>24</p>	<p>General Counters for SWS / DCEOs: General counters 2'6" ht from CTO side , table top 3'0" wide , customers top at 3'3" ht and 12" wide . All made in 19mm plywood and 1mm laminate for all vertical and inside areas and 1.5 mm thick Laminate for the table top , 20mm thick Granite for the customers top with edges duly beveled polished. Modesty panel should at least 12mm thick. One Key board tray and One pedestal 16" wide containing 2 draws and one flap door to be provides at every 4'6"gap (length of each counter 4'6"). All made in 19mm plywood and 1mm thick laminate even for the internal areas of the plywood. all draws and key board tray should be on telescopic channel and other hardware items as specified. All the edges of the plywood to be covered with 12mm thick steam beech beading duly melamine polished. All as per design and instructions of the design in charge.Cost must be inclusive of 12mm curved glass or straight glass front facia for the counters as per design.</p>	<p>25</p>	<p>Rft</p>		
<p>25</p>	<p>Cash Counter : Same as item no.24 but instead of Granite on customers top it should be in 15mm thick moulded glass top (12"x 54" x 15mm thick as per the design) and drawer pedestal size 18"wide with 4 draws with proper division made to keep different currency notes. AND cost should be inclusive of 12mm glass for front facia upto 5'0" from floor with proper slit provided for communication. All as per the instructions of the design in charge.</p>	<p>5</p>	<p>Rft</p>		

27	Low Height Storage Racks: Providing and installing of 18" deep storage racks , ht 2'6" / 3'0" / 5'0", length as per drg. All made in 19mm thick plywood and 9mm plywood for back side. All the exposed surfaces of plywood to be with 1mm thick laminate and top with 1.5mm thick laminate. inside side 1mm laminated 19mm plywood loose shelves to be provided at every 15" gap. Vertical supports should not exceed 3'0" gap and each door shutter size should not exceed 18" in width and 3'6" in ht. All hardware should be as per specs. All exposed edges of plywood should be with 12mm thick Steam beach wood molding duly melamine polished.All as per the instructions.	24	Sqft		
28	Full height Storage Racks: Same as item above but the height may vary from 4'0" to 8'0". All as per the Instructions.	250	Sqft		
29	Cheque Writing Desk with Voucher Box , Suggestion Box and Notice Board : Free standing Cheque writing desk and Slip box all made of 4"x1.5"thick steam beech wooden frame and 12mm glass as per design with slots for vouchers in glass. Wood to be melamine polished.	2	nos		
		SUB TOTAL D			
		TOTAL AMOUNT : II (SULTAN BAZAR BRANCH)			C+D

TOTAL AMOUNT : I (ZONAL OFFICE)	A+B :
TOTAL AMOUNT : II (SULTAN BAZAR BRANCH)	C+D :
GRAND TOTAL : I + II	:
DISCOUNTS IF ANY	:
TOTAL AMOUNT (After Discount)	: