

**NILESH G. BHAGAT**

Chartered Engineer, Architect & Chartered Valuer  
A-804, Jupiter, Vasant Galaxy, Off Link Road, Goregaon West, Mumbai 400 104.  
864, "Geet Govind", A/P. Katta, Taluka-Malvan, Dist: Sindhudurg 416 604.  
09833472133 nileshgbhagat@gmail.com

**PRICE BID (PART-I) -FURNITURE WORK AT BANK OF MAHARASHTRA, GOGOL, GOA**

No.	Description	Qty.	Unit	Rate	Amount
<b>1</b>	<b>GYPSON BOARD FALSE CEILING:</b> Providing & fixing as per design with suspended false ceiling consisting of 12mm.thk.Gyp. board suspended on G.I. framework to consists of G.I. perimeter channels 0.55 mm thk. x 20mm .x 30mm. along perimeter of false ceiling; screw fixed to wall/partition with nylon sleeves & screws @ 600mm. dc. Suspending GI. Intermediate channels of size 0.9mm thk.x45mmx15mm. from the soffit at max. distance 1220mm. dc with ceiling angle 0.55mm. thk.x2n5mm.x10mm. Fixed to soffit using proprietary supplied GI. Cleats & steel expansion fasteners. Ceiling section 0.55mm thk. xweb size 51.5mm & flanges 26mm. Each & 10.5 mm. lips fixed perpendicular to intermediate channel at 457mm. c/c Gyp board is screw fixed to ceiling section with 25mm. drywall screws at 230mm. c/c. boards to be finished with proprietary supplied jointing tape & jointing compound & sand papered to achieve a smooth finish etc. Complete or as directed by the Architect/Bank. Gyp ceiling where necessary as normal specification Rate should include all types of cut-outs, grooves ,moulding & plain troughs for tube lights / Down Lighter as directed by the designer. Note: Where RCC Slab is old and concrete is weak, the GI suspended channel shall be fixed with epoxy chemical and necessary load test to be carried out before fixing Gypsum board fixing. Rate shall be inclusive of epoxy chemical and fixing of suspenders with chemical	600	Sft.		
	Rate in words				
<b>2</b>	<b>ARMSTRONG FALSE CEILING:</b> Providing and fixing of Armstrong make Mineral fibre Ceiling Boards in true horizontal level suspended on inter locking Grid system made of Hot Dip Galvanized steel sections powder coated XL -15 mm as per manufacturers specification including making opening for electrical and air conditioning fitting complete as directed. The tiles and grid system FRAMEWORK XL-15 mm Main Runner of 3000mm spaced at 1200mm centre fixed to soffit by approved hangers at 1200mm distance. First and last hanger should not be at a distance more than 450mm from the adjacent wall.XL-15 mm 1200mm cross Tee to be interlocked between Main Runner at 600mm centre to form 1200x600mm module 600mmx600mm module to be formed by fixing XL-15mm 600mm Cross Tee between centre of 1200mm Cross Tees.19X19 mm Wall Angle to be secured to wall at 450mm centers Suspension to be done by using 2mm pre-straightened GI wire using anchor fasteners. Make - Armstrong - ANS Micro & Supra fine XL frame work. Note: Where RCC Slab is old and concrete is weak, the GI suspended channel shall be fixed with epoxy chemical and necessary load test to be carried out before fixing Gypsum board fixing. Rate shall be inclusive of epoxy chemical and fixing of suspenders with chemical	270	Sft.		
	Rate in words				
<b>3</b>	<b>LOW LEVEL PARTITION FOR CUBICALS:</b> Providing and fixing low height partition up to 5'height made out of 50 mm*50mm 18mm Gauge aluminium frames at 2' C/C vertically & horizontally with 6mm thick commercial plywood on both sides upto 3' height and above portion with 10mm toughened glass Finished with 1.00 thick laminate of approved shade and design. Basic rate of 6mm thick ply: 35/- Rs /sft. Basic rate of Laminate; 33/- Rs/sft	45	Sft.		
	Rate in words				
<b>4</b>	<b>SEMI GLAZED PARTITION WITH DOOR - BRANCH MANAGER CABIN</b> Providing & fixing 3" thick partly glazed partition with 10mm thick clear float glass for made up of 18 gauge 50x50 mm Aluminium section framework at 600 mm c/c both ways (or as directed by the Architect); 12 mm commercial plywood & 1 mm laminate from both sides. Partition should be finished with specified finish as per design. The rate includes providing 35 mm thick flush door finished with 1mm laminate of approved make/shade on both sides with necessary lipping patti polished. Rate includes all necessary hardware ( i.e ball bearing hinges of approved make, door closure, Cylindrical Lock with key, Door stopper etc) Exposed edges of the partition should have 75x12 mm matching wood Patti with groove in between. All provisions to be made for all electrical, networking, telephone etc. boxes onto partition framework at required heights/levels with necessary additional supports &/or scaffolding as required. The rate includes all necessary hardware & cleaning of partition to the satisfaction of the Architect etc. complete Basic rate of 12mm thick ply: 50/- Rs /sft. Basic rate of Laminate; 33/- Rs/sft	120	Sft.		
	Rate in words				
<b>5</b>	<b>SOLID PARTITION WITH DOOR IN SDV</b> Providing & fixing 3" thick solid partition for made up of 18 gauge 50x50 mm Aluminium section framework at 600 mm c/c both ways (or as directed by the Architect); 12 mm commercial plywood & 1 mm laminate from both sides. Partition should be finished with specified finish as per design. The rate includes providing 35 mm thick flush door with necessary lipping patti polished. Rate includes all necessary hardware ( i.e ball bearing hinges of approved make, door closure, Cylindrical Lock with key, Door stopper etc) Exposed edges of the partition should have 75x12 mm matching wood Patti with groove in between. All provisions to be made for all electrical, networking, telephone etc. boxes onto partition framework at required heights/levels with necessary additional supports &/or scaffolding as required. The rate includes all necessary hardware & cleaning of partition to the satisfaction of the Architect etc. complete	50	Sft.		
	Rate in words				
<b>6</b>	<b>Alterations to the existing partition with door (UPS cabin)</b> Carefully dismantling the partition and reusing the same with door and glass and placing the same as per the plan using necessary materials like ply, laminate, fittings, labour, transport, etc. complete as directed.	1	Job		
	Rate in words				
<b>7</b>	<b>Alterations to the existing glazed partition with door (Branch main entrance)</b> Carefully dismantling the partition and reusing the same with door and glass and placing the same as per the plan using necessary materials like fittings, labour, transport, etc. complete as directed.	1	Job		
	Rate in words				
<b>8</b>	<b>Alterations to existing Tables</b> Reusing the existing tables with necessary materials like locks, handles wherever necessary and placing the same as per the plan complete as directed. This work includes front vertical glass on the table top as per the standard specifications of the Bank.	3	No.		
	Rate in words				
<b>9</b>	<b>Alterations to Cash Counter</b> Carefully shifting the cash counter partition and reusing the same with door and glass and placing the same as per the plan using necessary materials like ply, laminate, fittings, labour, transport, etc. complete as directed.	1	No.		
	Rate in words				
<b>10</b>	<b>Officer/Clerk counter:</b>				

	Providing & fixing officers counter of 2'-6" height, 5' length and 2' 6" width, Counter to be made up of 18mm. thk. Plywood framework and open space for C.P.U. & small drawer above it on other side of Key Board drawer. The counter should have necessary holes of required sizes for wire managers. The counter should have necessary passages & ledges for data cables, electrical cables and telephone lines. The counter should be finished with 1.0mm. Thk. Laminate of approved colour & shade from external side and polish from inside. All the exposed edges of plywood including lower edges should have lipping patti. Lipping patti should be finished in polish. The cost should include necessary hardware Moulding .handles & Godrej make drawer locks with common key for cash drawers, footrest etc. complete as per design.	10	Rft		
	Rate in words				
<b>11</b>	<b>Alterations to existing wooden storage Units:</b>				
	Carefully removing and shifting the storage units, reusing and placing the same as per the plan using necseesary materials like fittings, labour, transport, etc. complete as directed.	1	Job		
	Rate in words				
<b>12</b>	<b>Storage Units:</b>				
	Providing & fixing storage units made up 18 mm. thk. plywood framework, 6 mm. thk. plywood back as required as per design. Good quality blockboard shutters should be fixed on SS heavy hinges Storage units. should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminate ed surfaces. All exposed edges of plywood should have lipping patti on it. Lipping patti should be finished with French polish on it. The cost should include necessary handles, magnetic catches, Godrej make locks etc. complete as per design.	168	Sft		
	Rate in words				
<b>13</b>	<b>Fixed glass partition</b>				
	Providing & fixing fixed glazed partition made up of 12 mm thk. Clear toughened glass shall be fixed in.Ozon / Enox make patch fitting with necessary hardware with application of sealant from all sides. Edge polish for all exposed sides of glass complete as directed.	50	Sft		
	Rate in words				
<b>14</b>	<b>Suggestion Box</b>				
	Providing & fixing box made up 18 mm. thk. plywood framework, 6/12 mm. thk. plywood back as required as per design. Good quality blockboard shutters should be fixed on brass hinges should be finished with 1mm. thk. laminate from external side & oil paint to non laminate ed surfaces. All exposed edges of plywood should have lipping patti on it. Lipping patti should be finished with French polish on it. The cost should include necessary handles, magnetic catches, Godrej make locks etc. complete as per design.	1	Nos		
	Rate in words				
<b>15</b>	<b>Cheque Drop Box</b>				
	Providing & fixing box made up 18 mm. thk. plywood framework, 6/12 mm. thk. plywood back as required as per design. Good quality blackboard shutters should be fixed on brass hinges should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminate ed surfaces. All exposed edges of plywood should have lipping patti on it. Lipping patti should be finished with French polish on it. The cost should include necessary handles, magnetic catches, Godrej make locks etc. complete as per design.	1	Nos		
	Rate in words				
<b>16</b>	<b>Aluminium Composite Paneling</b>				
	Aluminium Composite Panel (ACP) with framing of Aluminium Tube sections of min 1.5" x 1" and 20 gauge 2'-0" C/C both ways. Mirror screws to be used. Joints to be finished with Silicon based sealant. ACP thickness of 3 mm minimum of approved shade ( Silver-grey or equivalent as per Bank's Layout policy). ACP to be in 2' width panels or distributed equally. Alubond, Eurobond, Fujibond, Alco bond or equivalent ISO certified brands to be used. Shades to be as per bank's approval. Trap door will be 12 mm marine ply finished with ACP for rolling shutter wheel.				
	<b>Laminate and ply Paneling (Inside ATM and columns)</b>				
	Same as above but finished with 12mm thk. ply and 1mm thk. laminate	220	Sft		
	Rate in words				
<b>17</b>	<b>MIRROR IN TOILET BLOCK size 2'0x2'0</b>				
	P& F mirror Modi float in toilet block with 6mm bevelled on edges and fixed on SS Studs.	2	Nos		
	Rate in words				
<b>18</b>	<b>Oil Bound Distemper Paint</b>				
	Providing and application of cement/acrylic based putty of 3 Coats, Sanding of the surface free of undulations, application of 1 coat of primer and 2 coats of Oil Bound Distemper paint of approved make and shade as per layout policy	1500	Sft		
	Rate in words				
<b>18</b>	<b>MIRROR IN SDV size 5'0x2'0</b>				
	P& F mirror Modi float in SDV with 6mm bevelled on edges and fixed on SS Studs.	1	Nos		
	Rate in words				
<b>19</b>	<b>Wooden shelf in SDV size 9"x2'0</b>				
	P& F wooden shelf made of 18mm thk. ply finished with 1mm thk. laminate fitted ms brackets on the wall including all hardware and labour complete as directed.	1	Nos		
	Rate in words				
<b>20</b>	<b>MS Grill for ATM roof</b>				
	Providing and fixing ms grill of 25mmx5mm thk placed at 4" c/c over-lapping horizontally and vetically and welded to ISMC 75mm x40mm with intermediate supports to avoid sagging fitted with anchor bolts to the wall/beams complete with a coat od redoxide complete as directed.	45	Sft		
	Rate in words				
<b>21</b>	<b>9" Thk. laterite stone work</b>				
	Cutting the existing floor with electric cutter 6" deep for better interlocking of laterite stone without damaging the other tiles as per the plan and directions of the Architect. Providing and fixing laterite stone work upto 9'ht.and 9" thk in CM 1:4 finished with plaster in cement mortar on both sides. All the laterite stone work built including the wall shall be finished with neeru finish as directed complete.	150	Sft		
	Rate in words				
<b>22</b>	<b>Wooden shelf in dining near pantry 1'-6" x 5' -6"</b>				
	P& F wooden shelf made of 18mm thk. ply finished with 1mm thk. laminate fitted ms brackets on the wall including all hardware and labour complete as directed.	1	Nos		
	Rate in words				

23	<b>Glass divider between ATM machines ( 3'-0" x 5'-0" )</b>			
	Providing & fixing 12mm thk. toughened glass having machine polished edges with patch fittings complete as directed.	1	Nos	
	Rate in words			
24	<b>Electrical cabinet:</b>			
	Providing & fixing electrical cabinet made up 18 mm. thk. plywood 12" deep and Good quality blockboard shutters should be fixed on SS heavy hinges Storage units. should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminated surfaces. All exposed edges of plywood should have lipping patti on it. Lipping patti should be finished with polish on it. The cost should include necessary handles, magnetic catches, and EPC aluminium louvers 9" x6" - 4 nos. as approved complete as per design.	32	Sft	
	Rate in words			
25	<b>Wooden shelf for server size 2'-6" x 2'-0"</b>			
	P& F wooden shelf made of 18mm thk. ply finished with 1mm thk. laminate fitted ms brackets on the wall including all hardware and labour complete as directed.	1	Nos	
	Rate in words			
26	<b>Miscellaneous repairs and alterations</b>			
	Providing any necessary alterations and repairs required in the entire branch furnishing to hose any civil, wooden, AC works including necessary materails , labour , haulage, transport etc. complete as directed by the Bank.	1	Job	
	Rate in words			
				<b>GRAND TOTAL</b>
				<b>Add SGST</b>
				<b>ADD CGST</b>
				<b>TOTAL AMOUNT</b>

**Note: 1. The contractor shall quote rate of whole item in BOQ considering the provided basic rate of material by bank. However, if bank approves the basic rate of material below the provided rate in the respective item, than the difference of amount for that item will be deducted accordingly or rate will be reduced accordingly.**

**2.All the pages shall be signed and stamped by the contractor.**

**3.Price Bid shall be filled only in type form. The price bid which are handwritten will be summarily rejected.**

**4.No addition/alteration is permitted for contractor in BOQ.Also no discount in addition to the total is permitted in the BOQ.Contrcator has to fill the rates considering the specification of item, material,labour,trasporatation, taxes ,overhead charges, profit etc.**

Amount in Rupees:- Rs. \_\_\_\_\_

Sign & Seal of the Contractor : -

Date: