

**PROJECT: SANGAMNER BRANCH , DIST. AHAMEDNAGAR ,BANK OF MAHARASHTRA**  
**CLIENT: BANK OF MAHARASHTRA**  
**SITE :SANGAMNER BRANCH**

Sr. No.	Description	Qty.	Unit	Rate	Amount
	<b>INTERIOR WORK</b>				
1)	<b>Counters ( 10MM glass on table surface )</b> Providing, making & fixing low height Counter in any shape in 18 mm plywood top and 300 mm high 12 mm glass above the top top,vertcals finished with 1 mm laminates as per the design complete with drawers,locks,cable managers complete as per the dwg.	13.20	R.M.		
2)	<b>Cashier counter ( 10MM glass on table surface )</b> As above ,but height and other arrangements suitable for cashier.including toughened glass front glass partition and writing ledge	3.30	R.M.		
3)	Providing and fixing <b>MANAGER table ( 10MM glass on table surface )</b> as per the drawing including side table comprising of 3 No drawer and shutter box below the drawer as per drawing and to the entire satisfaction of the architects.	1.00	NO		
4)	<b>Officer's table ( 10MM glass on table surface )</b> A-Providing and fixing 5'-0" approx officer's table :- size and details as per drawings and to the entire satisfaction of the architects.	1.00	Nos.		
5)	<b>3'0" APPROX SERVER TABLE:</b> Providing & supplying side table approx. 3'0"x1'6"x2'6" high in hinges, piano hinges, tower bolts, stoppers, buffers, etc of standard make. As per drawing.	1.00	Nos.		
6)	<b>3'0" APPROX SIDE TABLE:</b> Providing & supplying side table approx. 3'0"x1'6"x2'6" high in hinges, piano hinges, tower bolts, stoppers, buffers, etc of standard make.	2.00	R.M.		
7)	<b>14" DEEP FULL HEIGHT STORAGE .</b> Providing & fixing storage cabinets of any length and height and 16" depth in 18mm thick comm. treated ply ,1.5 mm laminate stoppers, buffers, ball catches etc. of standard make	55.00	sq.m		
8)	<b>14" DEEP LOW HEIGHT STORAGE (both side Laminate Finish)</b> Providing & fixing storage cabinets of any length and height and 16" depth in 18mm thick comm. treated ply ,1.5 mm laminate stoppers, buffers, ball catches etc. of standard make	30.00	sq.m		
9)	<b>Low Ht.partitions with door</b> Providing & fixing 80mm thk. Partition 50x50 TW framing and 8 mm ply on both sides finished with 1.5mm thk approved laminate with soft bord panel at required places as directed , partition may have part 12mm toughned glass as per design.	10.00	sq.m		

10)	<p>Full Height Glazed partition with doors:-  Providing &amp; fixing 80mm thk. Partition 50x50 TW framing and 8 mm ply on both sides finished with 1.5mm thk approved laminate with soft bord panel at required places as directed , partition may have part 12mm glass as per design.  approved laminate, soft board panel or paint as directed,</p>	15.00	sq.m		
11)	<p>Fully glazed toughened glass partition with <b>Entrance door</b>  Providing and fixing ful ht. parttion in <b>12mm thk toughened glass</b> and locks as directed.</p>	10.00	sq.m		
12)	<p><b>Full height Partition</b>  Providing &amp; fixing 80mm thk. Partition 50x50 TW framing and 10 mm ply on both sides finished with 1.5mm thk approved laminate with soft bord panel at required places as directed.</p>	20.00	sq.m		
13)	<p><b>Notice Board:-Display Unit</b>  Providing and fixing notice board approx. 4' long and 4' high, all exposed surfaces,all complete as per drawings.</p>	3.00	sq.m		
14)	<p><b>Wall /coloumn Paneling/door frames with :-1.5 mm laminate</b>  Providing &amp; erecting 8 mm ply paneling to wall, columns with approved laminate of any colour to all ply surface</p>	45.00	sq.m		
15)	<p><b>Aluminium composite panel P &amp; F</b> Aluminium composite panel of Eurobond / equivalent. Including necessary ancillary work &amp; Including scaffolding .</p>	45.00	sq.m		
16)	<p><b>Fabrication work for porch construction</b> - providing &amp; making porch comprising of 50 x 50 x 6 to 18mm ISA framed structure with anchor fasteners bolted to the main structure, finished with redoxide and enamel paint. The mode of measurement shall be Total r.ft. of angle used for making the porch. Unit - smt.</p>	45.00	sq.m		
17)	<p><b>Armstrong tile False Ceiling/cladding :-</b> (Floor height 20' )  Providing &amp; fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 99 Prima tile with Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A.C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line &amp; level, including making grooves and trap doors for A.C unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges &amp; locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects. with framing scaffolding etc complete.note: Ceiling height - 20' )</p>	95.0	sq.m		

19)	<b>False Ceiling (Gypsum Board):</b> Providing & fixing in position false ceiling in Gypboard 12mm thick for horizontals & verticals fixed over G.I. framework as specified by India Gypsm Co. Ltd. including trap doors for A.C unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects. (Note:- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc. )	40.0	sq.m		
20)	<b>Roller blinds</b> Supplying and fixing best quality approved make in proper line and level complete with all necessary accessories. approved by engg.	14	Sq.m		
21)	<b>Luster Paint</b> to walls and ceiling/shutters/fabrication Providing lusture paint to walls with three coats of primer and 2 cote of putty and paint with cleaning etc. complete.	240.0	sq.m		
22)	<b>PROVIDING COLLAPSIBLE DOORS:</b> Providing and fixing collapsible doors made up of M.S.L. (40x4) angles frame with M.S. 'flat (20x5) @4 1/2" c/c dist. Including round boring @ top and bottom 1coat of red oxide primer & 2 coats oil paint etc.	15.0	Sqm		
23)	Providing 230mm thik B.B.M. in C.M. 1:6 in super structure etc. complete.	5.0	Cum		
24)	Providing and fixing Aluminium Sliding windows per drawing etc. complete.	12.0	Sqm		
25)	Providing and fixing MS windows Grill as per drawing etc. complete.	12.0	Sqm		
26)	Dismantling of 230mm thick brick work , Existing wall panneling, etc.with carting and cleaning .	10.0	Sqm		
27)	Providing and making 4 ' wide ramp as per drawing. ( black granite on top) or as per Architect	1.0	No.		
28)	Providing and fixing window and door granite frame with moulding .	12.0	Sqm		
29)	Closed the Mezzanine floor up side entry by M25 Grade Concrete with 12mm reinforcement steel , with 12mm bar cocncrete fshiring of bar etc. completed.	1.5	Cum		
30)	<b>Gypsum Plaster</b> Providing & applying 1/2" Ave. thick or as required and to the entire satisfaction of the Consultant.	40.0	Sqm		
<b>Total for furniture,Civil &amp; painting work</b>					
<b>Rs.</b> Note: Rate Including GST Taxes.					