

TENDER FOR

Proposed Electrical work

For

BANK OF MAHARASHTRA

NANDED MAIN BRANCH AT DISTT NANDED.

Issued for :

(ELECTRICAL WORK)

Owner

BANK OF MAHARASHTRA

ZONAL OFFICE

**PUSHAPAK PLAZA, GANESH NAGAR,
AUSA ROAD, LATUR**

Pramod Associates

Architect & Interior Designer,
LATUR

Assistant General Manager,
Bank of Maharashtra
Latur

Sub : **PROPOSED ELECTRICAL WORK FOR NANDED MAIN BRANCH AT
DISTT NANDED**

Sir,

I/We the undersigned have carefully gone through and clearly understood the plans, specifications, schedule of quantities, with General conditions for the above mentioned work and having VISITED & EXAMINED THE SITE of the proposed work, do hereby tender to execute and complete the entire work in accordance with the priced bill of quantified and/or as given in the special specification of each works attached hereto.

It is understood that the lowest or any tender will not necessarily be accepted and that you are not bound to assign any reason for the same.

I/we agree to keep our offer open for six months from the date of opening. Having examined the drawings, schedule of quantities relating to the proposed Tender for electrical work and having visited and examined the site of the proposed works and having acquired the tender invited by you, we the Undersigned hereby offer to execute, complete and maintain the proposed work in strict accordance with the specifications described in the Tender at the item rates quoted by us in the Tender for the sum of Rs._____ . We undertake to complete and deliver the total work within _____the date of issue of work order from you.

I/We also declare that I/We have not been blacklisted by any organization in Last three years.

Name and address of the contractor

Signature & Stamp of contractor

Place :

Date :

NAME OF WORK: PROPOSED ELECTRICAL WORK FOR NANDED MAIN BRANCH AT DISTT NANDED, FOR BANK OF MAHARASHTRA.

TENDER NOTICE

Sealed Item Rates Tenders are invited on behalf of **BANK OF MAHARASHTRA**, Zonal office Latur. From competent contractors, who have executed two or more works of similar nature satisfactorily during last three years. The contractors should be technically sound and financially capable.

The details are as under:

1. Name of Work: **PROPOSED ELECTRICAL WORK FOR NANDED MAIN BRANCH AT DISTT NANDED.**
2. Earnest Money Deposit by Pay Order or Demand Draft from Nationalized Bank(No Interest payable on this deposit) : Rs.5000/-
3. Tender Cost: Rs.500/- By cash/DD (non refundable)
4. Time of Completion: 15 days from the date of commencement
5. Issue of Tender: Tender Documents will be available from Bank of Maharashtra, Zonal office latur, From **21.06.2016** between 10.00 a.m to 5.00 p.m on the payment of Rs.500/-.
6. Submission of Tender : Sealed Tenders with the name of work subscribed on top of the cover will be received at, Bank of Maharashtra, Chief Manager-Incharge , Zonall office,Puspak Plaza,Ganesh Nagar,Ausa Road ,Latur. Last date of Tender submission is **28.06.2106** at 5.00 p.m.
7. Time & Date of Opening of tender : **01.07.2016** at 3.00 p.m.
8. Tender Rights : Conditional Tenders will not be accepted. The Bank reserves the right to accept or reject any or all the tenders without assigning any reason thereof or to accept any tender in part thereof.
9. Date of Commencement : Immediately.

Asst. General Manager,
Bank of Maharashtra,
Zonal office,Ganesh Nagar ,
Ausa road,
Latur

GENERAL CONDITIONS

(1) Sealed tender should be addressed to Chief Manager In charge , Bank of Maharashtra, Regional office, Puspak plaza,Ganesh Nagar,Ausa Road,Latur super scribed.

NAME OF WORK: PROPOSED ELECTRICAL WORK FOR NANDED MAIN BRANCH AT Distt NANDED.

1. The quotation will remain valid for a period of 6 months from the date of Openings of tenders. Bank reserves the right to accept or reject any or all the tenders without assigning any reason to do so. Bank does not bind itself for accepting the lowest quotation.
2. The tenderer should quote the rates in figures as well as in words.
3. All erasures, corrections and alterations made while filling the tender must be attested by initials of tenderer. Overwriting of the figures is not permitted.
4. The Bank reserves the right to reject any or all the quotations, accept part of any tender or entrust the entire work to any contractor or divide the work to more than one contractor (item wise) without assigning any reason or giving any explanation. The rates quoted by the contractor will hold good for this bifurcation and no compensation will be paid on this account.
5. Joint tenders shall not be considered.
6. Within 7 days of receipt of Intimation regarding acceptance of his tender by the Bank, the tenderer should send his acceptance of the work order in writing. If the tenderer does not do that, or does not start the work within 10 days of such intimation to him or fails to give justified reasons not to do so, acceptance of his tender would be withdrawn and Earnest Money

Deposit would be liable to be forfeited.

7. The rate quoted in the tender shall include all charges of scaffolding, lift, any tools and plants railway freight labour conditions and fluctuation in the rates, excise duty, sales tax, octroi and any other taxes or expenditure for carrying out the work.

8. Water and Electricity will be available free at site.

9. No Escalation in rates will be allowed under any circumstances.

10. The successful tenderer is bound to carry out entire work within stipulated

time limit. The tenderer will have to pay liquidated damages for non completion of job within stipulated period at the rate of Rs. 500/- per day after expiry of period of completion subject to maximum of 10 % of site contract value.

11. The successful tenderer is bound to carry out items of work necessary for completion of job even though the same are not included in the schedule of quantity. Rates of extra items will be derived from the tender. In case the rates do not exist in the tender and extra item is not similar to tender item, then the rates will be worked out on actual cost of material and labour, any other expenditure for completing that work plus 15 % towards contractor's profit & overheads. For this contractor must submit the rate analysis supported by original vouchers for purchase and labour.

12. The contractor must co-operate with other contractors appointed by the bank so that entire work shall proceed smoothly with least possible delay and to the satisfaction of the Bank.

13. The tenderor shall acquaint himself with the site conditions making his own arrangement for storing of material at site, lift, etc.

14. Contractor shall be prepared to work at times convenient to the Bank. No charges shall be paid for the same.

15. The contractor will attend to all defects noticed during defect liability period. If the contractor fails to attend the defects within a reasonable time these defects will be rectified by the Bank and the expenditure incurred on this account will be recovered from security deposit, or any other money due on to time.

16. The contractor shall make adequate arrangement for watch and ward of his material and shall ensure the safety, breakage and any theft of material fixed or unfixed by him or other sub contractor.

17. The work executed should be got approved by the Architect/Bank and

contractor shall rectify any bad workmanship pointed out at any stages and remove from site all the rejected material immediately.

18. The contractor shall be responsible for application of labour laws, compensation for injury and accident to person, whether employed by his or by his sub contractor.

19. The contractor will take necessary precautions for carrying out the work avoiding any damage to fixed or loose furniture, structures/decorative parts of the property. The contractor will rectify any damages done at his cost.

20. The contractor shall ensure that workmen employed by him for execution of work are suitably covered against workmen's Compensation Act, ESIS and other legislative enactments applicable to such works and workmen shall be to the contractor's account.

21. The contractor shall inform the Architect/Bank to check quality/measurements of any work which is likely to be hidden before covering.

22. In case of non-completion or delay in completion of work or removal of defects in time, the Bank shall be free to appoint another agency to get the job done at contractor's risk and cost.

23. Income Tax at applicable rate of the Bill Amount will be deducted at sources from the contractor's bill and will be deposited with the I.T.O. as per rules.

24. The Bank may delay the progress of work without, in any way, vitiating the contract and grant such extension of time for the commencement/completion of the contract as it may think proper and sufficient in consequence of such delay and the contractor shall not make claim for compensation or damage in relation there of.

25. The contractor will not execute any extra item or change in specification without Bank's permission in writing.

26. The quantities mentioned in the schedule of quantities are approximate. Payment will be made on actual work done by the contractor. However, the contractor should not deviate the quantity without Bank's permission.

27. Conditional tenders quoted by the tenderer is liable to be rejected.

28. The Bank has a right to alter the nature of work and to add or omit any items of work or to have the option of the same carried out departmentally or otherwise and such alternations or variations shall be carried out with out prejudice to this contract.

29. The Bank has right to terminate the contract, if the contractor abandons the work, or fails to commence and complete the work in time, or fails to abide by the contract conditions.

30. Measurements for all items shall be taken as per actual work done and no claim for any wastage in all material shall be considered.

31. Contractor must quote balanced rates as quantities mentioned in the tender are approximate and may vary to any extent. No extra rate shall be given on this account.

32. The contractor while executing the work during the working hours of the Bank shall take special care that disturbance is not created to Bank's staff and customer during the office hours. The contractor should also keep the banking hall in a reasonably good condition during banking hours.

33. THE RATES SHOULD BE FIRM INCLUDING ALL TAXES. DISCOUNT IN TOTAL AMOUNT WILL NOT BE CONSIDERED AND THE SAME TENDER WILL BE LIABLE FOR DISQUALIFICATION.

Name of Contractor with seal & signature

Date :

Place :

SPECIFICATION OF MATERIALS

All the material to be used shall be from the list of ISI approved Brand. Any deviation from this shall be got approved from Architect/Owner, the contractor shall submit samples of materials used for verifications and produce Bill in Original.

1. **SAMPLES** : After receipt of the bids but prior to award of the contract, bidder shall, upon notification from owner submit samples of materials he intends to use. The owner shall reserve the right to evaluate the sample with regard to the specification before award of work. Samples as directed by the Architect/Owner for various items shall be prepared/brought for approval without any cost.

SPECIAL CONDITIONS OF CONTRACT

1. Earnest Money Deposit : Rs. 5000/-
2. Initial Security Deposit (ISD) : Nil
3. Defects Liability Period : 12 months from the date of issue of virtual completion and handing over the site to bank.
4. Period of commencement : Immediately after issue of Letter of Intent/Work Order.
5. Stipulated period for completion : 15 days
:
6. Retention Money : 5 % retention money from each running Bill.
7. Terms of Rate : The rates shall be at site of work and should be inclusive of all taxes including works contract tax, VAT if any
8. Period of validity of Tender : Six months from the date of opening tender
.
9. Period for honouring interim certificate: 7 working days from the date of Architect's certificate.
10. Period of honouring final bill certificate from Architect : 10 working days from the receipt of final bill.
11. Period of honouring final bill certificate : 10 working days from date of Architect's certificate.
12. Validity of rates after award of Tender : "NO ESCALATION IN PRICE WILL BE ALLOWED"

13. Release of Retention Money : Retention Money shall be released after satisfactorily completion of Defects Liability period of 12 months.

BANK OF MAHARASHTRA

Name of work : **Proposed Electrical work for NANDED MAIN BRANCH AT DISTT NANDED , for Bank of Maharashtra.**

GENERAL SUMMARY OF COST

I. ELECTRICAL WORK - Rs. _____

TOTAL Rs. _____
(RUPEES)

Name of Contractor with seal & signature

Date :

Place :

Bill for Electrical work Bank Of Maharashtra Branch Nanded Main
Date :- 20-06-2016

SR. NO.	DESCRIPTION OF ITEM	UNIT	QUNTITY	RATE	AMOUNT
1	Providing & fixing 1x40 watt mirolta tube set of Philips make on walls etc. complete.	NO.	18		
2	Providing & fixing 23 watt Energy saver lamps of Philips or any other approved make on walls etc. complete.	NO.	11		
3	Providing & fixing 6Amp light/fan/tube point in concealed type at given position with polycap wire and Anchor make switches etc. complete.	NO.	70		
4	Providing & fixing Bell /Telephone points at given in concealed manner including wire etc. complete	NO.	14		
5	Providing & fixing 32 AMP TPN switches as incomer of L&T or HPL make with M.S. enclosure etc. complete.	NO.	1		
6	Providing & fixing 18 way simer distribution board (double door)with MCB of required AMP.Etc.complete	NO.	1		
7	Providing &fixing RCCB 100 AMP 4pole with M.S. enclosures etc. complete	NO.	1		
8	Providing & fixing one half point on switch boards etc. complete.	NO.	12		
9	Providing & fixing call bell of Anchor make at required position etc complete.	NO.	2		

10	Providing & fixing LED ceiling fitting false ceiling mounted square light rectangular light etc. complete	NO.	40		
11	Providing & Fixing 48" dia ceiling fan of crompton / Usha make etc. complete.	NO.	15		
12	Providing & Fixing 12" dia exhaust fan of approved make etc. complete	NO.	2		
13	Providing & Fixing 24" dia ceiling fan of Crompton / Usha make etc. complete.	NO.	1		
14	Providing Earth pit with copper plate size 300mmx300mmx4mm GI pipe complete with connection with 14 SWG copper wire from earth pit to required point one for U.P.S one for general lighting / computers/Gesset, All for A.C etc. complete.	NO.	2		
15	Providing & Fixing 16 Amp power points with 2.5Sq.mm ply cap wire etc. complete.	NO.	5		
16	Providing & Fixing 100 Amp 4pole change over switch with M.S. enclosure etc. complete.	NO.	1		
17	Providing & Laying 1.5sqmm spare wire from distribution board to each switch board for inverter wiring etc. complete.	L.S	1		
18	Providing & fixing AC in 4sq. mm copper wire with 25AMP single pole mcb in suitable box point in concealed type at given position with Anchor wire and Anchor make mcb etc. complete.	NO.	2		
19	Fan point wiring (ceiling fan point with electronic regulator) pipehook, anchor fastener given position with polycap wire and Anchor make Modular switches etc. complete	NO.	16		
20	Providing & laying DB to Each work station AC wiring & earthing in 2x 4sq. mm & 1x1.50sq.mm earthing copper wire point in concealed type at given position with Anchor wire etc. complete.	RMT.	260		

21	Providing & laying DB to Each switch board station Circuit point wiring & earthing wiring in 2x2.50sqr. Mm & 1x1.50sqr. mmcopper wire point in concealed type at given position with Anchor wire etc. complete.	RMT.	118		
22	Providing & laying RCCB DB to UPS DB work station UPS incomer wiring in 2x 10sqr. mm copper wire point in concealed type at given position with Anchor wire etc. complete.	RMT.	109		
23	Providing & saddling of 4 core x 6 sq. mm copper armed cable of polycap make from meter to TPN switch to Distribution board etc. complete.	RMT.	22		
	Computer Wiring	-			
24	Providing & fixing 2 pole MCB of 40 Amp with M.S.enclosure of UPS in out supply etc. complete	NO.	4		
25	Providing & fixing 10 way simer UPS in put out put ditribution board (double door) with 32 amp MCB of required AMP etc. complete	NO.	2		
26	Providing &fixing UPS power points consisting of 4no. 6AMP switches & 4no.6 AMP sockets on each board etc. complete .	NO.	15		
27	Providing & laying UPS DB to Each switch board station UPS Circuit point wiring & earthing wiring in 3x2.50sqr.mm copper wire for earthing point in concealed type at given position with Anchor wire etc. complete.	RMT.	148		
28	Providing & Fixing of D- link make CAT-6data cable HUB/SWITCH to each workstation.	RMT.	405		
29	Providing & Fixing of CAT-610 box	NO.	16		
30	Providing & Fixing of 2mtr long CAT-6 patch cord	NO.	15		
31	Providing & Fixing of RJ -45 connector with crimping.	NO.	20		
32	Providing & Fixing of D- link make 16port SWITCH	NO.	1		
33	Supling & Fixing of 6 U RACK	NO.	1		
34	split A/C 5 star model 1 ton	NO.	1		
35	split A/C 5 star model 1.5 ton	NO.	1		

36	split A/C 5 star model 2. ton	NO	7		
37	cooling pipe coper indor to out door A/C cooling pipe	NO.	240		
	TOTAL				